


**All States Rentals, Inc.**

PO Box 94258, Las Vegas, NV 89193
1-800-276-0744

5-16-2003



Mr. Robert P. McIntyre
Nassau County Solid
Waste Management
441 N. Kings Road
Callahan, Fl. 32011
ph.#904-321-5770 FB.
Ph.#904-879-6321 Callahan
Fax#904-879-6323

Re: Quotation For Refuse Compaction System

Good Day Mr. McIntyre;

The following quotation reflects placing three compactors, one at the Jail, new Judicial complex, and one at the existing Nassau county courthouse annex building.

- Purchase One each new Accurate model#265X-35 cubic yard self contain compactor/container which feature:
- a) Keylock start/stop, Full container light, Pressure boost jog control on 15' sealtite.
 - b) NEMA 12 weather proof gasketed control panel/Complete UL listed/10HP TEFC motor-208, 230, or 460 volt 3 phase/Meets ANSI Z 245.2 safety standards/10HP remote power pack with two 8' long hydraulic hoses.
 - c) Double end pickup/Fixed breaker bar teeth/1/4" understructure rails/Full gasketed dump door/Fire ports both sides of container sides.

Options to meet Nassau County installation needs:

- A) Multi cycle timer (Compactor ram cycles 3 times before shutting down).
- B) Totally enclosed steel doghouse hopper with lockable side door and access interlock switch.
- C) Ram stop forward (closes off charge box opening to enhance security)
- D) Color coded pressure gauge (works off actual pressures of compactor or to help county employees determine fullness of compactor).
- E) Ram stop forward (enhances security to prevent prisoners from escape inside compactor).
- F) 15' long container guides with stops.

Net 30 Day Terms

Above described equipment-invoiced by Accurate \$ 15482.50 EACH

Freight FOB Alexandria, La. to Nassau County, Fl. 640.00 EACH

Installation by BFI and includes: Anchor 15' 650.00 EACH
long guides & stops, Remote power pack and
place compactor on customer supplied concrete
pad to be 6" thick 3000# reinforced 12' wide X
long. Electrical connection from customer

APPROVEDDATE 8-25-03 JKB

**All States Rentals, Inc.**PO Box 94258, Las Vegas, NV 89193
1-800-276-0744

Page Two

Purchase continued supplied fused knife disconnect box(to be located within 5' of remote power pack)to control panel on remote power pack. Provide Nassau County employees instruction satrtup and saftey operation.

Grand total from page one \$ 16772.50EACI
\$16772.50 x 3 compactors= \$50317.50

Warrantny 3 years Structure, 1 year Components, 6 months Labor

Rent

All States Rentals would rent above described equipment including freight delivery and installation costs. ALL Maintenance and Parts during the term of contract, or for as long as contract is in effect. All States Rentals retains ownership of equipment.

Five year contract \$ 394.45 per month EACH x 3 =\$1183.35

Six year contract \$ 331.30 per month EACH x 3 = \$993.90

The compactors proposed can be handled by Nassau County and BFI rolloff equipment.

Please feel free to contact me at cell401-935-5180 or my home office 386-441-3050 should any questions develop. Delivery and installation could occur in four weeks from date of order.

Sincerely,



Gary Fenner

10 HP

MOTOR H.P.	VOLTAGE	FULL LOAD AMPS	WIRE FEED TO MOTOR (COPPER)	DUAL ELEM FUSES	CIRCUIT BREAKERS	WIRE TO FEED (0-100FT) DISCONNECT	WIRE TO FEED (100-250 FT.) DISCONNECT	MIN. DISC SIZES
5 HP	460-3φ	7.0	12 GAUGE	15 AMP	15 AMP	12 GAUGE	10 GAUGE	30 AMP
5 HP	230-3φ	14.0	12 GAUGE	20 AMP	20 AMP	10 GAUGE	8 GAUGE	30 AMP
5 HP	208-3φ	14.8	12 GAUGE	20 AMP	20 AMP	10 GAUGE	8 GAUGE	30 AMP
10 HP	460-3φ	13.0	10 GAUGE	17.5 AMP	20 AMP	10 GAUGE	8 GAUGE	30 AMP
10 HP	230-3φ	26.0	10 GAUGE	35 AMP	40 AMP	8 GAUGE	4 GAUGE	60 AMP
10 HP	208-3φ	28.0	10 GAUGE	40 AMP	50 AMP	8 GAUGE	4 GAUGE	60 AMP
10 HP	220-1φ	40.0	6 GAUGE	60 AMP	60 AMP	4 GAUGE	2 GAUGE	250V-60 AMP
15 HP	460-3φ	20.0	10 GAUGE	25 AMP	30 AMP	8 GAUGE	6 GAUGE	30 AMP
15 HP	230-3φ	40.0	8 GAUGE	50 AMP	30 AMP	4 GAUGE	2 GAUGE	60 AMP
15 HP	208-3φ	44.0	6 GAUGE	50 AMP	60 AMP	4 GAUGE	2 GAUGE	60 AMP
20 HP	460-3φ	25.0	10 GAUGE	30 AMP	40 AMP	6 GAUGE	4 GAUGE	60 AMP
20 HP	230-3φ	50.0	6 GAUGE	60 AMP	70 AMP	4 GAUGE	2 GAUGE	100 AMP
20 HP	208-3φ	55.0	4 GAUGE	70 AMP	70 AMP	4 GAUGE	2 GAUGE	100 AMP
30 HP	460-3φ	40.0	8 GAUGE	50 AMP	60 AMP	6 GAUGE	2 GAUGE	60 AMP
30 HP	230-3φ	80.0	3 GAUGE	100 AMP	100 AMP	2 GAUGE	1/0 GAUGE	100 AMP
30 HP	208-3φ	88.0	2 GAUGE	110 AMP	125 AMP	1 GAUGE	1/0	100 AMP
60 HP	460-3φ	77.0	2 GAUGE	90 AMP	100 AMP	2 GAUGE	1/0 GAUGE	100 AMP
60 HP	230-3φ	154.0	3/0	180 AMP	200 AMP	1/0	4/0	200 AMP
30 HD +ROTO	220-1φ	140.0	1/0 2/0	125 AMP 150 AMP	125 AMP 150 AMP	1/0 2/0	DO NOT RECOMMEND	200 AMP

Commissioner Vanzant, and unanimously carried to approve and to authorize the Chairman to sign a contract with the Harbor Branch of Environmental Laboratories, Inc. for water sampling for Nassau-Amelia Utilities.

6:12 Upon the request and recommendation of the Clerk, it was moved by Commissioner Deonas, seconded by Commissioner Acree, and unanimously carried to approve a payment in the amount of \$34,297.50 to the City of Fernandina Beach for island wide beach monitoring pursuant to the interlocal agreement dated October 9, 2002, with the funding source identified as the Beach Fund. Mr. Oxley stated that these funds would be applied to the boat ramp at the north end of Amelia Island.

6:14 Upon the request and recommendation of the Clerk, it was moved by Commissioner Deonas and seconded by Commissioner Acree to approve a trash compactor for the Judicial Complex at \$300 per month to be furnished by All States Rentals, Inc., P. O. Box 94258, Las Vegas, Nevada 89193 as a sole source provider. It was noted that this would require a pad, approximately 12' x 30', and electricity as an additional expense, with an approximate installation cost of \$2,000 to \$3,000. The motion carried unanimously.