


**All States Rentals, Inc.**

PO Box 94258, Las Vegas, NV 89193
1-800-276-0744

5-16-2003



Mr. Robert P. McIntyre
Nassau County Solid
Waste Management
441 N. Kings Road
Callahan, Fl. 32011
ph.#904-321-5770 FB.
Ph.#904-879-6321 Callahan
Fax#904-879-6323

Re: Quotation For Refuse Compaction System

Good Day Mr. McIntyre;

The following quotation reflects placing three compactors, one at the Jail, new Judicial complex, and one at the existing Nassau county courthouse annex building.

- Purchase One each new Accurate model#265X-35 cubic yard self contain compactor/container which feature:
- a) Keylock start/stop, Full container light, Pressure boost jog control on 15' sealtite.
 - b) NEMA 12 weather proof gasketed control panel/Complete UL listed/10HP TEFC motor-208, 230, or 460 volt 3 phase/Meets ANSI Z 245.2 safety standards/10HP remote power pack with two 8' long hydraulic hoses.
 - c) Double end pickup/Fixed breaker bar teeth/1/4" understructure rails/Full gasketed dump door/Fire ports both sides of container sides.

Options to meet Nassau County installation needs:

- A) Multi cycle timer (Compactor ram cycles 3 times before shutting down).
- B) Totally enclosed steel doghouse hopper with lockable side door and access interlock switch.
- C) Ram stop forward (closes off charge box opening to enhance security)
- D) Color coded pressure gauge (works off actual pressures of compactor to help county employees determine fullness of compactor).
- E) Ram stop forward (enhances security to prevent prisoners from escape inside compactor).
- F) 15' long container guides with stops.

Net 30 Day Terms

Above described equipment-invoiced by Accurate \$ 15482.50 EACH

Freight FOB Alexandria, La. to Nassau County, Fl. 640.00 EACH

Installation by BFI and includes: Anchor 15' 650.00 EACH
long guides & stops, Remote power pack and
place compactor on customer supplied concrete
pad to be 6" thick 3000# reinforced 12' wide X
long. Electrical connection from customer

APPROVED

DATE 8-25-03 JKB

**All States Rentals, Inc.**PO Box 94258, Las Vegas, NV 89193
1-800-276-0744

Page Two

Purchase continued supplied fused knife disconnect box(to be located within 5' of remote power pack)to control panel on remote power pack. Provide Nassau County employees instruction satrtup and saftey operation.

Grand total from page one \$ 16772.50EACI
\$16772.50 x 3 compactors= \$50317.50

Warranty 3 years Structure, 1 year Components, 6 months Labor

Rent

All States Rentals would rent above described equipment including freight delivery and installation costs. ALL Maintenance and Parts during the term of contract, or for as long as contract is in effect. All States Rentals retains ownership of equipment.

Five year contract \$ 394.45 per month EACH x 3 =\$1183.35

Six year contract \$ 331.30 per month EACH x 3 = \$993.90

The compactors proposed can be handled by Nassau County and BFI rolloff equipment.

Please feel free to contact me at cell401-935-5180 or my home office 386-441-3050 should any questions develop. Delivery and installation could occur in four weeks from date of order.

Sincerely,



Gary Fenner

10 HP

| MOTOR H.P. | VOLTAGE | FULL LOAD AMPS | WIRE FEED TO MOTOR (COPPER) | DUAL ELEM FUSES | CIRCUIT BREAKERS | WIRE TO FEED (0-100FT) DISCONNECT | WIRE TO FEED (100-250 FT.) DISCONNECT | MIN. DISC SIZES |
|-------------|---------|----------------|-----------------------------|--------------------|--------------------|-----------------------------------|---------------------------------------|-----------------|
| 5 HP | 460-3φ | 7.0 | 12 GAUGE | 15 AMP | 15 AMP | 12 GAUGE | 10 GAUGE | 30 AMP |
| 5 HP | 230-3φ | 14.0 | 12 GAUGE | 20 AMP | 20 AMP | 10 GAUGE | 8 GAUGE | 30 AMP |
| 5 HP | 208-3φ | 14.8 | 12 GAUGE | 20 AMP | 20 AMP | 10 GAUGE | 8 GAUGE | 30 AMP |
| 10 HP | 460-3φ | 13.0 | 10 GAUGE | 17.5 AMP | 20 AMP | 10 GAUGE | 8 GAUGE | 30 AMP |
| 10 HP | 230-3φ | 26.0 | 10 GAUGE | 35 AMP | 40 AMP | 8 GAUGE | 4 GAUGE | 60 AMP |
| 10 HP | 208-3φ | 28.0 | 10 GAUGE | 40 AMP | 50 AMP | 8 GAUGE | 4 GAUGE | 60 AMP |
| 10 HP | 220-1φ | 40.0 | 6 GAUGE | 60 AMP | 60 AMP | 4 GAUGE | 2 GAUGE | 250V-60 AMP |
| 15 HP | 460-3φ | 20.0 | 10 GAUGE | 25 AMP | 30 AMP | 8 GAUGE | 6 GAUGE | 30 AMP |
| 15 HP | 230-3φ | 40.0 | 8 GAUGE | 50 AMP | 30 AMP | 4 GAUGE | 2 GAUGE | 60 AMP |
| 15 HP | 208-3φ | 44.0 | 6 GAUGE | 50 AMP | 60 AMP | 4 GAUGE | 2 GAUGE | 60 AMP |
| 20 HP | 460-3φ | 25.0 | 10 GAUGE | 30 AMP | 40 AMP | 6 GAUGE | 4 GAUGE | 60 AMP |
| 20 HP | 230-3φ | 50.0 | 6 GAUGE | 60 AMP | 70 AMP | 4 GAUGE | 2 GAUGE | 100 AMP |
| 20 HP | 208-3φ | 55.0 | 4 GAUGE | 70 AMP | 70 AMP | 4 GAUGE | 2 GAUGE | 100 AMP |
| 30 HP | 460-3φ | 40.0 | 8 GAUGE | 50 AMP | 60 AMP | 6 GAUGE | 2 GAUGE | 60 AMP |
| 30 HP | 230-3φ | 80.0 | 3 GAUGE | 100 AMP | 100 AMP | 2 GAUGE | 1/0 GAUGE | 100 AMP |
| 30 HP | 208-3φ | 88.0 | 2 GAUGE | 110 AMP | 125 AMP | 1 GAUGE | 1/0 | 100 AMP |
| 60 HP | 460-3φ | 77.0 | 2 GAUGE | 90 AMP | 100 AMP | 2 GAUGE | 1/0 GAUGE | 100 AMP |
| 60 HP | 230-3φ | 154.0 | 3/0 | 180 AMP | 200 AMP | 1/0 | 4/0 | 200 AMP |
| 30 HD +ROTO | 220-1φ | 140.0 | 1/0 2/0 | 125 AMP 150 AMP | 125 AMP 150 AMP | 1/0 2/0 | DO NOT RECOMMEND | 200 AMP |