

BOCC Agenda Item
Golder Associates Proposal 993-3928.82 West Nassau Closure and 2008 Financial Assurance Documentation

Agenda Request For: April 9, 2008

Department: County Coordinator

Background: A request for proposal was sent to Golder Associates dated February 26, 2008 for engineering services for Task 1-Planning of the Active West Nassau Landfill Closure Project and Task 2-2008 Annual Financial Assurance Documentation & Report. Task 1 was requested as part of the ongoing review of landfill options. Task 2 is a required annual analysis and report due to FDEP by August 31 in compliance with Florida Administrative Code 62-701-630.

Response to the proposal request was received March 13, 2008 with an optional Task 3 added by Golder. Please refer to attached documentation for further detail of each task. Fiscal summary of proposal response is as follows:

- Task 1-Planning of the Active West Nassau Landfill Closure Project \$28,606
- Task 2-2008 Annual Financial Assurance Documentation \$21,811
- Task 3-Evaluation of Alternatives to Early Closure \$5,037

Task 2 is specifically budgeted for in account 70341534-531302 Professional Svc-Golder at \$22,000 and funds are available for Tasks 1 & 3 in account 70341534-531450 Prof Svc-Operational and Financial. Please refer to attached "Funding for Golder Proposal Dated 3/31/08 993-3928.82" attachment.

Financial/Economic Impact to Future Years Budgeting Process or Effect on Citizens: The work products will be utilized during the current landfill options analysis assisting in determining the resulting financial model for Nassau County's solid waste disposal responsibilities. The 2008 Annual Financial Assurance Documentation is budgeted each year and is the foundation for the annual closure and post-closure escrow deposits and adjustments. 2007 Annual Financial Assurance process cost was \$21,350.

Action requested and recommendation: Request Board consideration of the following Tasks:

1. ~~Task 1-Planning of the Active West Nassau Landfill Closure Project \$28,606~~
2. Task 2-2008 Annual Financial Assurance Documentation \$21,811
3. ~~Task 3-Evaluation of Alternatives to Early Closure (optional) \$5,037~~

Is this action consistent with the Nassau County Comprehensive Land Use Plan?
Public Facility Element Section 4


Funding Source: ~~Task 1 \$28,606 account 70341534-531450~~
Task 2 \$21,811 account 70341534-531302
~~Task 3 \$5,037 account 70341534-531450~~

APPROVED BOCC

DATE 4/9/08 BKA

Approved Task #2 and Continued
Task #1 & #3 to 4/16/08

BOCC Agenda Item
Golder Associates Proposal 993-3928.82 West Nassau Closure and 2008 Financial
Assurance Documentation

Reviewed by:	<u>Print Name:</u>	<u>Signature & Date:</u>
Department Head	<u>TED SELBY</u>	<u> 3/25/08</u>
Legal	<u>David Hallman</u>	<u>SENT 3/25/08</u>
County Coordinator	<u>Ed Sealover</u>	<u> 3/25/08</u>
Finance	<u>Gene Knaga</u>	<u>SENT 3/25/08</u>
Administrative Services	<u>Ted Selby</u>	<u> 3/25/08</u>
Grants	<u>N/A</u>	<u>_____</u>

Revised 10/07

Nassau County Board of County Commissioners
Solid Waste Management Fund
Funding for Golder Proposal Dated 3/13/08 993-3928.82
In Response to Request of 2/26/08

<u>Task#</u>	<u>Task Description</u>	<u>Funding Source</u>	
		<u>Account</u>	<u>Amount Available</u>
1	Planning of the Active West Nassau Landfill Closure Project	\$ 28,606 70341534-531450	\$ 66,695
2	2008 Annual Financial Assurance Documentation	\$ 21,811 70341534-531302	\$ 22,000
3	Evaluation of Alternatives to Early Closure (added-optional)	\$ 5,037 70341534-531450	\$ 38,089
Total		\$ 55,454	

	<u>Available Budget</u>
<u>account 70341534-531450 Prof Svc-Operational and Financial</u>	\$ 100,000
less GSG/NGN phase I BCC approved 12/6/07	\$ (33,305)
available budget before Golder .82 proposal	\$ 66,695
Task 1	\$ (28,606)
after Task 1	\$ 38,089
Task 3	\$ (5,037)
after Task 3	\$ 33,052
 <u>account 70341534-531302 Professional Svc-Golder</u>	
Specifically budgeted \$22,000 for this annual task in account	\$ 22,000

Golder Associates Inc.

9428 Baymeadows Road, Suite 400
Jacksonville, FL USA 32256-7979
Telephone (904) 363-3430
Fax (904) 363-3445



VIA E-MAIL ONLY

March 13, 2008

993-3928.82

Nassau County Board of County Commissioners
96160 Nassau Place
Yulee, Florida 32097

Attention: Ms. Cathy Lewis, CPA
Senior Administrative Services Analyst

**RE: PROPOSAL TO PROVIDE ENGINEERING SERVICES
FOR PLANNING THE ACTIVE WEST NASSAU
LANDFILL CLOSURE PROJECT
AND 2008 ANNUAL FINANCIAL ASSURANCE DOCUMENTATION
NASSAU COUNTY, FLORIDA**

Dear Ms. Lewis:

Golder Associates Inc. (Golder) is pleased to submit this proposal to the Nassau County Board of County Commissioners (Board) for providing professional services associated with assisting the Board in planning the potential early closure of the West Nassau Landfill and with preparation of the 2008 annual financial assurance documentation. This proposal provides Golder's proposed scope of services based on your Request for Proposal (RFP) dated February 26, 2008 and discussions between the issuance of the RFP and the date of this proposal. This proposal also includes a schedule for performing the various tasks, cost estimate, and terms and conditions. It should be noted that Golder and our teaming partner, S2Li, have prepared this proposal together and S2Li will be performing the majority of the work under Task 2, as has been the case over the last seven years. S2Li will also be involved in the work effort under Tasks 1 and 3.

As a point of clarification, we understand that the tasks to be performed for the planning of the closure project include estimating costs for work to be conducted by Golder and others (i.e., the landfill closure contractor) at various points in the future and that these costs are intended to be used for County budgeting purposes. Given the nature of predicting costs in the future and for work to be performed by others, Golder's cost estimates produced as part of this work will be on the conservative side and will include various contingencies.

SCOPE OF SERVICES

Task 1: Planning of the Active West Nassau Landfill Closure Project

Based on the description of the scope of services provided in the RFP, we have divided Task 1 into four subtasks as follows:

- Subtask 1A – Prepare Detailed Task List for Early Closure
- Subtask 1B – Prepare Cost Estimate for Early Closure through Post Closure
- Subtask 1C – Prepare Detailed Schedule for Early Closure
- Subtask 1D – Prepare Report and Present to Board

The scope of services for each of the subtasks are presented in the following sections. It should be noted that Golder and S2Li envision that the work under Task 1 will require a close working relationship with County staff so that a realistic approach to early closure can be developed, one that matches the County's requirements with its goals and allows the regulatory requirements to be incorporated. Therefore, the scope will include one or more meetings with the appropriate staff to assure that we are all "on the same page". We believe that a realistic task list, cost estimate, and schedule can be produced based on our working relationship to date, along with our familiarity with the facility and the regulations.

Subtask 1A – Prepare Detailed Task List for Early Closure

Under this subtask Golder and S2Li will prepare a detailed task list and description of activities required to close the West Nassau Landfill early (i.e., within 2-3 years). This task list is limited to the work that is required at the landfill itself and does not include concurrent activities that are needed to assure the County's waste is disposed properly elsewhere.

The task list will include the regulatory requirements and permit requirements, including re-design and closure plan revision, along with, based on our knowledge of the site conditions, activities that may be required in the transition between closure of the gates and actual closure construction. Presently, we would envision that one of the first tasks to be undertaken, based upon the direction of the Board, would be to engage the Florida Department of Environmental Protection (FDEP) in the process to inform them of the intention of the Board and to assure them that the proper steps are being taken to close the landfill in accordance with all regulatory and permit requirements. Therefore, we have included under this task attendance of one representative each from Golder and S2Li at a meeting with County staff to discuss the approach for early closure with FDEP, followed by a meeting at FDEP's Jacksonville office (to be attended by appropriate County staff as well). For planning and costing purposes, it is assumed that these meetings will be held on the same day. Many of the tasks will be developed based on specific discussions and decisions made at the FDEP meeting. This task will also include a detailed task list of requirements for post closure care, after the cover system is constructed, including operation and maintenance of the leachate collection system and the landfill gas collection and treatment system, along with general maintenance of the site.

Subtask 1B – Prepare Cost Estimate for Early Closure through Post Closure

Based on the task list developed under Subtask 1A, Golder and S2Li will develop a cost estimate for the early closure of the landfill. The cost estimate will be prepared on a task-by-task basis

(as much as practical) so that there is enough detail for the Board to understand the various uncertainties and contingencies. The cost estimates will be based on recent project experience, including the recent permit renewal effort and the recent partial closure at West Nassau (including the bidding process, contractor costs, and project oversight and certification), experience on other projects, and our knowledge of the site conditions. The cost estimate will also include an estimate of the post-closure care requirements.

As discussed above, our understanding is that the Board desires this cost estimate for budgeting purposes, so that it can plan for the costs associated with the landfill for the upcoming two to three fiscal years. Based on this understanding, Golder's cost estimates presented as part of this project will be conservative and will include various contingencies. Golder's cost estimates will be based on recent experience and will utilize adjustment factors as necessary to provide reasonable costs on a 2008 cost basis. Given that the project through completion of the closure construction will likely take on the order of 3 years, we will provide costs based on today's inflation factors.

Subtask 1C – Prepare Detailed Schedule for Early Closure

Golder will prepare a detailed schedule that includes each of the tasks developed under Subtask 1A. The schedule, however, will likely include ranges (as opposed to fixed time frames) that are flexible based on several factors, including the desired start date that we will work with the County to set and the possible time frames to meet regulatory requirements. The schedule will need to incorporate, based on discussions with the County, the requirements for obtaining Board approvals along the way (if necessary) and time for the procurement process from the County. Depending on the variability in the initial schedule prepared, we may prepare one or two optional schedules to best represent the range of possible schedules for this project.

For preliminary planning purposes, we have prepared a schedule with general items that will hopefully give the County an overall look at the potential schedule for this project. The preliminary schedule is attached to this proposal. It should be noted that this is a preliminary schedule based on what we know of the project at this point; we believe that this schedule is representative of the major tasks to be completed and this will be the starting point for the detailed schedule.

Subtask 1D – Prepare Report and Present to Board

Golder will prepare a report for submittal to the County that presents the task list, cost estimate, and schedule (prepared under subtasks 1A through 1C). The report will provide a summary of the approach taken for development of each of the items and any assumptions that were made during the preparation. We will also develop a summary presentation for the purposes of presenting the information collected and the report to the Board at a meeting to be designated by County staff.

Task 2: 2008 Annual Financial Assurance Documentation

Golder and S2Li will perform the annual financial assurance documentation for the County's three landfills (West Nassau (closed and active), Bryceville, and Lofton Creek) for submittal to FDEP by September 1, 2008. As for the past seven years for which work has been conducted, S2Li conducts the majority of the documentation, calculations, and document

preparation; Golder provides an update on operational changes, and serves as a reviewer and overall project manager. The tasks and costs described below assume that the County will contract for and provide the aerial photograph of the West Nassau Landfill to Golder/S2Li in AutoCAD format; that the County will provide the quantity and composition of waste disposed of in the Active West Nassau Landfill from the date of the 2007 landfill aerial to the date of this year's aerial; except for the closure cost of the active portion of the West Nassau Landfill, that all of the financial forms for the landfills show that this year's costs are increased by an inflation factor only (which is expected as of this date); that no costs associated with early closure of the landfill are included¹; and that the costs for post-closure have not increased from last year. The following subsections detail the scope for each task, as proposed.

Subtask 2A – Facility Inspections

Facility inspections will be conducted so that the conditions of the landfills can be documented by a third party engineer, as required by FDEP. S2Li will visit each landfill with a representative of the County and complete the landfill inspection forms for the County's use. The inspection forms will note any deficiencies that require correction.

Subtask 2B – Remaining Capacity/Fill Time Calculations

Initially, the airspace consumed over the last year will be calculated using last year's and this year's aerial surveys. The remaining airspace for the facility will be calculated based on this year's aerial and the ultimate build-out drawing (from permit). The remaining landfill space and timing to reach capacity, including the waste contribution from the west sideslope closure construction activities, will also be calculated. We will also evaluate the change to the amount of waste landfilled due to the elimination of the special residential assessment and the reduction of the gate fees that occurred on October 1, 2007. Two cross sections will be prepared showing north-south and east-west contours and final grades for use in the FDEP report. An overlay figure will also be prepared of this year's aerial topographic map and final grade plan.

Subtask 2C - FDEP Forms and Letter

The required FDEP Forms will be completed for each landfill along with a letter of transmittal that will detail the work performed, the rationale behind the calculations and costing approach. Any changes in the various cost items, e.g., additional groundwater or surface water monitoring requirements, will be incorporated into the forms. Additionally, the closure costs for the active portion of the closure estimate will be increased by 10% to account for the increases cost of oil affecting the costs of liner materials, piping, and transportation of all materials to the site. These forms are required to be signed by the Chairman of the Board of County Commissioners and signed and sealed by a registered Professional Engineer in the State of Florida. Draft reports will be submitted to the County for review. Upon receipt of comments from the County, the reports will be revised as necessary, signed and sealed by a registered Professional Engineer, and submitted to FDEP and the County.

¹ We believe this is the best approach for the 2007-2008 annual financial assurance documentation, i.e., to prepare the required documents as if the landfill will continue operating (based on recent waste acceptance, etc.). If the decision is made by the Board of County Commissioners that early closure is desired, updated financial assurance documentation will be required with the closure permit.

Task 3: Evaluation of Alternatives to Early Closure (Optional)

Although not requested by the RFP, Golder proposes to provide an evaluation of some of the possible alternatives to final closure at the landfill prior to reaching capacity. This task would involve reviewing the regulatory requirements for maintaining an inactive status, reviewing regulatory requirements for remaining active status (with minimal waste being accepted), and evaluate the possibility of having an outside source fill the landfill with potentially non-municipal solid waste (which could generate revenue and minimize costs for early closure due to fill and grading requirements). This task is optional under this task order, but Golder believes that this exercise could potentially allow the County to best utilize the remaining airspace at the landfill.

SCHEDULE

Golder and S2Li are prepared to begin work on this work order upon notification of approval by the Board. Based on the scope of services described above, we have estimated a six-week schedule for preparing the detailed task list, cost estimate, and schedule under Task 1. This time frame is estimated based partially on the often difficult task of scheduling a meeting with FDEP, and that meeting is critical to development of all phases of the work; we will work diligently to complete these tasks as soon as possible after authorization. Under Task 2, work will begin upon cost proposal approval, with the scheduling of the site visits under Task 2A. Work under Task 2B will begin upon receipt of the aerial survey data from the County, and Task 2C will be conducted concurrently with Task 2B. The draft reports for the County will be submitted such that corrections and finalization can be made to allow for obtaining County signatures, signing and sealing by the Professional Engineer, and submittal prior to August 31, 2008.

COST ESTIMATE

Golder's cost estimate to complete the work as described in the above scope of services is \$55,454. A detailed breakdown of the costs for each task and the labor and expenses estimated are included in the attached Table 1. The costs associated with the components of the work to be conducted by S2Li are included under Direct Expenses, Subcontractor Costs, and as per our agreement, S2Li is not marked up like other subcontractors. It should be noted that the costs for Task 2, Financial Assurance Documentation, have only slightly increased over last year's costs and there are additional evaluations to be conducted. As for all our projects, the Board will only be billed actual hours and expenses incurred on the project for work within the agreed scope of services. Direct expenses, such as shipping costs, will be marked-up 10 percent for administrative purposes. Travel and communications costs (except for specific field activities, as estimated in Table 1) will not be billed to Nassau County as stated in our August 1998 proposal. The cost estimate will not be exceeded without prior authorization from the Board.

TERMS AND CONDITIONS

This work will be performed under the Agreement for Consulting Services between Golder and the County, dated February 22, 1999.

Nassau County Board of County Commissioners
Ms. Cathy Lewis, CPA

- 6 -

March 13, 2008
993-3928.82

Golder appreciates this opportunity to provide our services to Nassau County. If you have any questions regarding this cost proposal, please do not hesitate to call.

Sincerely,

GOLDER ASSOCIATES INC.



Wendy D. Karably
Senior Consultant/Principal

cc: Mr. Omar Smith, S2Li

FN: G:\Projects\993\993-39\993-3928\82\Early Closure Planning FA.docx

TABLE 1

Cost Estimate
 Planning for Early LF Closure and 2008 Financial Assurance
 West Nassau Landfill
 Callahan, Nassau County, Florida

LABOR		LABOR CATEGORY AND RATE										TOTAL HOURS	SUBTOTAL LABOR
		Practice Leader	Senior Consultant	Senior Engineer	Sen. Proj. Engineer	Project Engineer	Staff Engineer II	Engineer I	Drafting	Technician	Admin		
TASK	DESCRIPTION	\$185	\$160	\$135	\$120	\$100	\$90	\$75	\$85	\$60	\$60		
1A	Detailed Task List for Early Closure	0	20	0	0	30	0	10	0	0	4	64	\$7,190
1B	Cost Estimate for Early Closure thru Post Closure	0	10	0	0	24	0	8	0	0	4	46	\$4,840
1C	Detailed Schedule for Early Closure	0	10	0	0	20	0	8	0	0	8	46	\$4,680
1D	Report Preparation & Presentation to Board	0	10	0	0	20	0	2	0	0	8	40	\$4,230
2A	Facility Inspections	0	2	0	0	0	0	0	0	0	0	2	\$320
2B	Remaining Capacity/Fill Time Calculations	0	4	0	0	0	0	0	0	0	0	4	\$640
2C	FDEP Forms and Letter	0	5	0	0	4	0	0	0	0	0	9	\$1,200
3	Evaluation of Alternatives to Early Closure (Optional)	0	8	16	0	4	0	0	0	0	2	0	\$3,960
TOTALS:		0	69	16	0	102	0	28	0	0	26	211	\$27,060

EXPENSES		Field Vehicle (day)	Rental Car Site Visits (day)	Field Equipment & Materials (est.)	Mileage (mile)	Shipping Costs (est.)	AutoCAD Charges (hr)	Photocopies (pg.)	Color Copies (pg.)	Drawing Reproduction (est.)	Office Services Fee (7% of Labor)	Subcontractor (\$2Li)	SUBTOTAL EXPENSES
TASK	DESCRIPTION	\$100	\$80	\$0.485	\$0.485	\$20	\$20	\$0.15	\$2				
1A	Detailed Task List for Early Closure	0	0	\$0	0	NA	NA	NA	0	\$0	\$503	\$3,000	\$3,503
1B	Cost Estimate for Early Closure thru Post Closure	0	0	\$0	0	NA	NA	NA	0	\$0	\$339	\$1,000	\$1,339
1C	Detailed Schedule for Early Closure	0	0	\$0	0	NA	NA	NA	25	\$150	\$328	\$1,000	\$1,528
1D	Report Preparation & Presentation to Board	0	0	\$0	0	NA	NA	NA	25	\$150	\$296	\$800	\$1,296
2A	Facility Inspections	0	0	\$0	0	NA	NA	NA	0	\$0	\$22	\$2,500	\$2,522
2B	Remaining Capacity/Fill Time Calculations	0	0	\$0	0	NA	NA	NA	0	\$0	\$45	\$7,000	\$7,045
2C	FDEP Forms and Letter	0	0	\$0	0	NA	NA	NA	0	\$0	\$84	\$10,000	\$10,084
3	Evaluation of Alternatives to Early Closure (Optional)	0	0	\$0	0	NA	NA	NA	0	\$0	\$277	\$800	\$1,077
TOTALS:		\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$100	\$300	\$1,894	\$26,100	\$28,394

COST SUMMARY

TASK	DESCRIPTION	SUBTOTAL LABOR	SUBTOTAL EXPENSES	SUB-TASK TOTALS	TASK TOTALS
1A	Detailed Task List for Early Closure	\$7,190	\$3,503	\$10,693	TASK 1: \$28,606
1B	Cost Estimate for Early Closure thru Post Closure	\$4,840	\$1,339	\$6,179	
1C	Detailed Schedule for Early Closure	\$4,680	\$1,528	\$6,208	
1D	Report Preparation & Presentation to Board	\$4,230	\$1,296	\$5,526	
2A	Facility Inspections	\$320	\$2,522	\$2,842	TASK 2: \$21,811
2B	Remaining Capacity/Fill Time Calculations	\$640	\$7,045	\$7,685	
2C	FDEP Forms and Letter	\$1,200	\$10,084	\$11,284	TASK 3: \$5,037
3	Evaluation of Alternatives to Early Closure (Optional)	\$3,960	\$1,077	\$5,037	
TOTALS		\$27,060	\$28,394	\$55,454	\$55,454

**PRELIMINARY SCHEDULE FOR EARLY CLOSURE
WEST NASSAU LANDFILL**

MONTH	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
ITEM 1 - Includes notifications (FDEP, citizens, etc.), closure plan revision, operations plan revision, closure cover redesign, closure permitting, FDEP review, addressing RAIs.	█																																			
ITEM 2 - Includes preparation of construction cost estimate, preparation of bidding documents, bid advertisement, pre-bid meeting, award of bid, notice-to-proceed.										█																										
ITEM 3 - Includes closure construction and certification.																		█																		

NOTES:

This schedule does not include the procurement of alternative waste handling activities.

This schedule should be considered preliminary as there are several factors (i.e., alternative waste handling, FDEP review, County's procurement process, etc.) that could affect the time frames represented above.

Cathy Lewis

From: Karably, Wendy [Wendy_Karably@golder.com]
Sent: Thursday, March 13, 2008 2:55 PM
To: Cathy Lewis
Cc: Omar E. Smith, P.E.
Subject: Proposal for Early Landfill Closure Planning and Financial Assurance Documentation
Importance: High
Attachments: Early Closure Planning FA.pdf

Cathy,

As you requested, Golder has prepared the attached proposal for assisting the County with planning for the early closure of the landfill, and for the preparation and submittal of the Annual Financial Assurance Documentation. Please do not hesitate to call if you have any questions or would like to discuss the proposal further.

Thanks,

Wendy

Wendy Karably

Principal

Golder Associates Inc.
9428 Baymeadows Road
Suite 400
Jacksonville, Florida
Ph: 904-363-3430
Fax: 904-363-3445
wkarably@golder.com



NASSAU COUNTY
BOARD OF COUNTY COMMISSIONERS
P.O. Box 1010
Fernandina Beach, Florida 32035-1010

Jim B. Higginbotham Dist. No. 1 Fernandina Beach
Michael H. Boyle Dist. No. 2 Amelia Island
Tom Branan Dist. No. 3 Yulee
Barry Holloway Dist. No. 4 Bryceville
Marianne Marshall Dist. No. 5 Callahan

JOHN A. CRAWFORD
Ex-Officio Clerk

DAVID A. HALLMAN
County Attorney

EDWARD L. SEALOVER
County Coordinator

February 26, 2008

Wendy Karably, Senior Consultant/Principal
Golder Associates
9428 Baymeadows Road, Suite 400
Jacksonville, FL 32256-7979
TRANSMITTED VIA EMAIL

RE: REQUEST FOR PROPOSAL TO PROVIDE ENGINEERING SERVICES
1. CLOSURE OF WEST NASSAU LANDFILL PROJECT
2. 2008 ANNUAL FINANCIAL ASSURANCE DOCUMENTATION & REPORT

TASK 1-PLANNING OF THE ACTIVE WEST NASSAU LANDFILL CLOSURE PROJECT

Scope of Services-Detail process, timeline and costs associated with closure and post-closure of the current active West Nassau Landfill assuming closure process to begin as soon as practical. Include timeline with critical dates, activity identification and detail cost calculations, incorporating of FDEP regulations, permit references and other data to quantify what is required and at what cost for closure and subsequent post closure of active West Nassau landfill.

Project deadline-Earliest possible date after acceptance of task proposal by Board of County Commissioners

TASK 2-2008 ANNUAL FINANCIAL ASSURANCE DOCUMENTATION & REPORT

Scope of Services-Prepare documentation and report, as required by Florida Administrative Code 62-701.630, which you have prepared for the last seven years. It is anticipated that work performed under TASK 1-REQUEST FOR CLOSURE OF WEST NASSAU LANDFILL PROJECT will be updated and utilized to some degree for this task. This task includes active West Nassau landfill and closed West Nassau, Bryceville and Lofton Creek landfills.

Project deadline-In compliance with FAC 62-701.630, which in 2007 was August 31st.

Contact me with questions and submit proposal directly to me. Thank you.

Cathy Lewis
Administrative Services Department
904-491-7370
clewis@nassaucountyfl.com

(904) 491-7380 or (800) 789-6673

An Affirmative Action / Equal Opportunity Employer