

SECTION 00 63 63

CHANGE ORDER REQUEST FORM

PROJECT Henry Smith Road Improvements Project

No. 0003

DATE OF ISSUANCE 04/18/2025

EFFECTIVE DATE 04/18/2025

NASSAU COUNTY BOARD OF COUNTY COMMISSIONERS

COUNTY Contract No.: CM 3670

CONTRACTOR- CGC, Inc

ENGINEER / ARCHITECT- Peters & Yaffee, Inc.

Description of changes:

Refer to the following attachment for description:: Change Order No. 0003..
 FDOT Concurrence by email is attached.

Attachments: (List documents supporting change) Engineers Estimate; C0#3 Plan Sheets; CO#3 Schedule of Values

CHANGE IN CONTRACT PRICE:

Original Contract Price

\$ 2,334,871.35

CHANGE IN CONTRACT TIMES:

Original Contract Times

Substantial Completion: 120 days (02/24/2025)
(days and dates)Ready for Final Payment: 140 days (03/16/25)
(days and dates)

Net change from previous Change Orders No. 1 to No. 2

\$ -10,643.40

Net change from previous Change Orders No. 1 to No. 2

120

(days)

Contract Price prior to this Change Order

\$ 2,324,227.95

Contract Times Prior to This Change Order

Substantial Completion: 240 days (06/24/2025)

(days and dates)

Ready for Final Payment: 260 days (07/14/2025)
(days and dates)

Net Increase (decrease) of this Change Order

\$ 5,426.00

Net Increase (decrease) of this Change Order

1

(days)

Contract Price with all approved Change Orders

\$ 2,329,653.95

Contract Times with all approved Change Orders

Substantial Completion: 241 days (06/25/2025)

(days and dates)

Ready for Final Payment: 261 days (07/15/2025)
(days and dates)

RECOMMENDED:

By: Dow Peters
Engineer/Architect (Authorized Signature)

Date: 5/12/2025

APPROVED:

By: Raymond Allure
COUNTY (Authorized Signature)

Date: 5/12/2025

ACCEPTED:

By: Richard Cannon Gaskin, Jr.
Contractor (Authorized Signature)

Date: 7/2/2025

CHANGE ORDER APPROVAL FORM

PROJECT: HENRY SMITH ROAD IMPROVEMENTS PROJECT

CHANGE ORDER NUMBER: 0003

DATE: May 12, 2025

CONTRACT NUMBER: CM3670

PURCHASE ORDER NUMBER (IF APPLICABLE): 24000640

TO CONTRACTOR: CGC, Inc.

Description: Change order 0003 captures adjustments made for mitered end sections and drainage changes.

Reason for Change Order: Due to existing field conditions changes were made to accommodate new mitered end sections. Details listed below.

The Construction Plans call for the installation of 13" x 17" Elliptical Corrugated Metal Pipe (ECMP) Mitered End Sections (MES) at S-1 (Station 13+26.91 LT, Pine Street) and S-2 (13+28.56 RT, Pine Street). The existing pipe at this location was in fact 15" x 21" ECMP not 13" x 17" ECMP as noted in the plans. 15" x 21" ECMP MES's were installed in lieu of the 13" x 17" ECMP MES's detailed in the plans. Price increase: \$2,738.00

The Construction Plans call for 15" x 21" ECMP MES's at stations 133+90.69 and 134+29.80 RT. The existing 15" x 21" pipe was severely degraded and replaced with 18" High-Density Polyethylene (HDPE) pipe by Nassau County. As a result, 18" CMP MES's were installed in lieu of the 15" x 21" ECMP MES's detailed in the plans. Zero price change

The Construction Plans call for 15" Corrugated Metal Pipe (CMP) MES's at stations 170+61.2 and 171+00 RT. The existing 15" pipe was severely degraded and replaced with 18" HDPE pipe by Nassau County. As a result, 18" CMP MES's were installed in lieu of the 15" CMP MES's detailed in the plans. Price increase: \$1,258.00

The Construction Plans call for 15" Reinforced Concrete Pipe (RCP) MES's at stations 172+47.2 and 172+98.73 RT. The existing pipe was in fact 15" Polyvinyl Chloride (PVC) instead of 15" RCP so 15" CMP MES's were installed in lieu of the 15" RCP MES's detailed in the plans. Price decrease: \$628.00

The Construction Plans call for 5LF of 24" RCP at MES S-5 (Station 175+48.66 LT). The existing 24" CMP that the proposed 24" RCP was supposed to connect to was severely degraded. 3LF of the existing 24" CMP was removed and replaced with 3LF of 24" RCP. The new total of RCP at the subject location increased from 5LF to 8LF. Price increase: \$2,058.00

Original Contract Sum.....	\$ <u>2,334,871.35</u>
Net Change by Previous Change Order/Supplemental Agreement.	\$ <u>-10,643.40</u>
Contract Sum Prior to This Change Order.....	\$ <u>2,324,227.95</u>
Amount of this Change Order (Add).....	\$ <u>+5,426.00</u>
New Contract Sum Including this Change Order.....	\$ <u>2,329,653.95</u>

The Contract Time will be **increased or decreased (select one)** Increased 1 days
 Previous Substantial Completion: 240 (6/24/2025) Previous Final Completion: 260 (7/14/2025)
 New Substantial Completion: 241 (6/25/2025) New Final Completion: 261 (7/15/2025)

APPROVED BY: <u>Robert Companion</u> Department Head/Managing Agent	DATE: <u>8/4/2025</u>
APPROVED BY: <u>Janice Melmore</u> Procurement	DATE: <u>8/14/2025</u>
APPROVED BY: <u>Chris Lacambra</u> Office of Management and Budget	DATE: <u>8/13/2025</u>
APPROVED BY: <u>Denise C. May, Esq., BCS</u> County Attorney	DATE: <u>8/15/2025</u> <u>dl</u>
APPROVED BY: <u>[Signature]</u> County Manager	DATE: <u>8/15/2025</u>
APPROVED BY: <u>N/A</u> Chairman	DATE: _____
ATTEST: <u>N/A</u> Mitch L. Keiter, Clerk of Courts	DATE: _____

Account No(s). 63470541-563100 HSMTH

Change Order No. 0003

Project: Henry Smith Road Improvements Project
Contract No.: CM3670
Financial Project No.: 438178-1-54-01
Contractor: CGC, Inc.

Nassau County - Project Manager
Scott Pedigo, P.E.
spedigo@nassaucountyfl.com

CGC, Inc. - Project Manager
Jonny Barton
jbarton@cgcivil.com


- The contractor was directed to not work on January 22, 2025, due to inclement weather (snow). One contract day is being granted because of this directive.
- The Construction Plans call for the installation of 13" x 17" Elliptical Corrugated Metal Pipe (ECMP) Mitered End Sections (MES) at S-1 (Station 13+26.91 LT, Pine Street) and S-2 (13+28.56 RT, Pine Street). The existing pipe at this location was in fact 15" x 21" ECMP not 13" x 17" ECMP as noted in the plans. 15" x 21" ECMP MES's were installed in lieu of the 13" x 17" ECMP MES's detailed in the plans.
 - Price increase: \$2,738.00
- The Construction Plans call for 15" x 21" ECMP MES's at stations 133+90.69 and 134+29.80 RT. The existing 15" x 21" pipe was severely degraded and replaced with 18" High-Density Polyethylene (HDPE) pipe by Nassau County. As a result, 18" CMP MES's were installed in lieu of the 15" x 21" ECMP MES's detailed in the plans
 - Net zero price change
- The Construction Plans call for 15" Corrugated Metal Pipe (CMP) MES's at stations 170+61.2 and 171+00 RT. The existing 15" pipe was severely degraded and replaced with 18" HDPE pipe by Nassau County. As a result, 18" CMP MES's were installed in lieu of the 15" CMP MES's detailed in the plans.
 - Price increase: \$1,258.00
- The Construction Plans call for 15" Reinforced Concrete Pipe (RCP) MES's at stations 172+47.2 and 172+98.73 RT. The existing pipe was in fact 15" Polyvinyl Chloride (PVC) instead of 15" RCP so 15" CMP MES's were installed in lieu of the 15" RCP MES's detailed in the plans
 - Price decrease: \$628.00


- The Construction Plans call for 5LF of 24" RCP at MES S-5 (Station 175+48.66 LT). The existing 24" CMP that the proposed 24" RCP was supposed to connect to was severely degraded. 3LF of the existing 24" CMP was removed and replaced with 3LF of 24" RCP. The new total of RCP at the subject location increased from 5LF to 8LF.
 - Price increase: \$2,058.00


Refer to the attached Engineer's Estimate for details regarding the adjusted quantities and costs.

Engineer's Estimate

Adjusted Quantities & Costs								
SOV Item No.	Pay Item No.	Item Description	Unit	Plan Qty.	Qty. Change	New Qty.	Unit Price	New Cost
22	0430-982-623	13" x 17" MES ECMP CD	EA	2	-2	0	\$4,918.00	\$0.00
24	0430-984-123-1	15" MES RCP	EA	2	-2	0	\$5,972.00	\$0.00
25	0430-984-123-2	15" MES CMP	EA	8	0	8	\$5,658.00	\$45,264.00
27	0430-984-125-2	18" MES CMP	EA	14	4	18	\$6,287.00	\$113,166.00
29	0430-984-625	15" x 21" MES ECMP	EA	8	0	8	\$6,287.00	\$50,296.00
19	0430-175-124	Drainage Pipe 24" RCP	LF	5	3	8	\$686.00	\$5,488.00
							New Total:	\$214,214.00
							Org. Total:	\$208,788.00
							Change:	\$5,426.00







Invitation to Bid

HENRY SMITH ROAD IMPROVEMENTS PROJECT

NC23-022RR-ITB

**REVISED
BID PRICE SHEET
HENRY SMITH ROAD IMPROVEMENTS PROJECT**

ITEM NO.	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	0101-1	MOBILIZATION	LS	1	\$337,967.00	\$337,967.00
2	0102-1	MAINTENANCE OF TRAFFIC	LS	1	\$151,090.00	\$151,090.00
3	0104-10-3	SEDIMENT BARRIER	LF	1,762	\$3.00	\$5,286.00
4	0104-11	FLOATING TURBIDITY BARRIER	LF	84	\$30.00	\$2,520.00
5	0104-18	INLET PROTECTION SYSTEM	EA	3	\$250.00	\$750.00
6	0107-1	LITTER REMOVAL	AC	54	\$325.00	\$17,550.00
7	0107-2	MOWING	AC	51	\$455.00	\$23,205.00
8	0110-1-1	CLEARING AND GRUBBING	LS	1	\$481,982.00	\$481,982.00
9	0110-4-10	REMOVAL OF EXISTING CONCRETE	SY	233	\$30.00	\$6,990.00
10	0120-1	REGULAR EXCAVATION	CY	122	\$30.00	\$3,660.00
11	0120-6	EMBANKMENT	CY	106	\$30.00	\$3,180.00
12	0160-4	TYPE B STABILIZATION	SY	80	\$20.00	\$1,600.00
13	0285-701	OPTIONAL BASE GROUP 1	SY	599	\$23.00	\$13,777.00
14	0285-706	OPTIONAL BASE GROUP 6, TYPE B-12.5	SY	77	\$120.00	\$9,240.00
15	0327-70-16	MILLING EXISTING ASPHALT CONCRETE, 1/2" AVG DEPTH	SY	23,323	\$2.20	\$51,310.60
16	0334-1-52	SUPERPAVE ASPHALT CONCRETE SP-9.5 (TRAFFIC B, PG-76-22)	TN	2,534	\$205.00	\$519,470.00
17	0339-1	MISCELLANEOUS ASPHALT PAVEMENT	TN	125	\$478.00	\$59,750.00
18	0430-174-118	DRAINAGE PIPE, 18" RCP	LF	15	\$556.00	\$8,340.00
19	0430-175-124	DRAINAGE PIPE, 24" RCP	LF	5	\$686.00	\$3,430.00
20	0430-175-215	DRAINAGE PIPE, 15" X 17" ECMP	LF	5	\$600.00	\$3,000.00

ITEM NO.	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
21	0430-982-129	MITERED END SECTION, 24" RCP, CD	EA	1	\$7,490.00	\$7,490.00
22	0430-982-623	MITERED END SECTION, 13"X17" ECMP, CD	EA	2	\$4,918.00	\$9,836.00
23	0430-982-635	MITERED END SECTION, 13"X17" ECMP, CD	EA	4	\$12,540.00	\$50,160.00
24	0430-984-123-1	MITERED END SECTION, 15" RCP, SD	EA	2	\$5,972.00	\$11,944.00
25	0430-984-123-2	MITERED END SECTION, 15" CMP, SD	EA	8	\$5,658.00	\$45,264.00
26	0430-984-125-1	MITERED END SECTION, 18" RCP, SD	EA	2	\$6,646.00	\$13,292.00
27	0430-984-125-2	MITERED END SECTION, 18" CMP, SD	EA	14	\$6,287.00	\$88,018.00
28	0430-984-623	MITERED END SECTION, 13"X17" ECMP, SD	EA	2	\$4,918.00	\$9,836.00
29	0430-984-625	MITERED END SECTION, 15"X21" ECMP, SD	EA	8	\$6,287.00	\$50,296.00
30	0522-2	CONCRETE DRIVEWAY, 6" THICK	SY	189	\$120.00	\$22,680.00
31	0524-1-1	CONCRETE DITCH PAVT, NON REINFORCED, 4"	SY	29	\$500.00	\$14,500.00
32	0530-3-4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	17	\$604.00	\$10,268.00
33	0530-74	BEDDING STONE	TN	10	\$705.00	\$7,050.00
34	0536-1-1	GUARDRAIL - ROADWAY, GENERAL TL-3	LF	1,638	\$39.00	\$63,882.00
34	0536-7-3	SPECIAL GUARDRAIL POST - ENCASED POST FOR SHALLOW MOUNT	EA	21	\$325.00	\$6,825.00
36	0536-73	GUARDRAIL - REMOVAL	LF	2,351	\$8.00	\$18,808.00
37	0536-85-20	GUARDRAIL END TREATMENT TRAILING ANCHORAGE	EA	1	\$4,225.00	\$4,225.00
38	0536-85-24	GUARDRAIL END TREATMENT - PARALLEL APPROACH TERMINAL	EA	15	\$4,225.00	\$63,375.00
39	0570-1-2	PERFORMANCE TURF, SOD	SY	7,794	\$6.00	\$46,764.00
40	700-1-11	SINGLE POST SIGN, FURNISH & INSTALL, UP TO 12 SF, GROUND-MOUNT	AS	8	\$600.00	\$4,800.00
41	700-1-12	SINGLE POST SIGN, FURNISH & INSTALL, 12-20 SF, GROUND MOUNT	AS	1	\$1,000.00	\$1,000.00

ITEM NO.	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
42	700-1-50	SINGLE POST SIGN, RELOCATE	AS	3	\$300.00	\$900.00
43	700-1-60	SINGLE POST SIGN, REMOVE	AS	8	\$150.00	\$1,200.00
44	701-18-101	PROFIED THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.828	\$11,830.00	\$9,795.24
45	705-10-1	OBJECT MARKER, TYPE 1	EA	3	\$500.00	\$1,500.00
46	705-10-2	OBJECT MARKER, TYPE 2	EA	15	\$600.00	\$9,000.00
47	705-10-3	OBJECT MARKER, TYPE 3	EA	4	\$700.00	\$2,800.00
48	706-1-1	RAISED PAVEMENT MARKERS, TYPE B	EA	499	\$5.15	\$2,569.85
49	711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	114	\$10.00	\$1,140.00
50	711-11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2	\$360.00	\$720.00
51	711-14-191	THERMOPLASTIC, PREFORMED, 12" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	42	\$33.00	\$1,386.00
52	711-14-193	THERMOPLASTIC, PREFORMED, 6" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	96	\$20.00	\$1,920.00
53	711-16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.909	\$7,540.00	\$21,933.86
54	711-16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.284	\$7,540.00	\$24,761.36
55	711-16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.341	\$2,535.00	\$864.44

BASE BID TOTAL

TOTAL AMOUNT (ITEMS 1 TO 55)

\$ \$2,334,871.35

(Figures)

Two Million Three Hundred Thirty Four Thousand Eight Hundred Seventy One Dollars
Thirty Five Cents

(Use Words)

All specific cash allowances are included in the price(s) set forth above and have been computed in accordance with paragraph 11.02 of the General Conditions.



Outlook

RE: Henry Smith - Change Order No. 0003 For Review

From Evans, Kimberly <Kimberly.Evans@dot.state.fl.us>

Date Mon 4/28/2025 12:00 PM

To Jose Vazquez Jr <jvazquez@wsbeng.com>

Cc Scott Pedigo <spedigo@nassaucountyfl.com>; George J. Murray <gmurray@nassaucountyfl.com>; Raymond C. Albury <ralbury@nassaucountyfl.com>; Bill Glennon <wglennon@wsbeng.com>; Josh Dalager <jdalager@wsbeng.com>

 2 attachments (4 MB)

RE: 438178-1-54-01 - Henry Smith - Change Order No. 0003 For Review - Change Order 3 for review; Change Order No. 0003 Final FOR REVIEW.pdf;

EXTERNAL EMAIL

Good Morning,

Please see Change Order #3 concurrence below..

Thanks,



Kim Evans, CPM, FCCM

Program Management
Local Programs Section – MS
2014

1109 South Marion Avenue
Lake City, Florida 32025
386-961-7402

kimberly.evans@dot.state.fl.us



“Be the change you want to see”

From: Jose Vazquez Jr <jvazquez@wsbeng.com>

Sent: Tuesday, April 22, 2025 11:28 PM

To: Evans, Kimberly <Kimberly.Evans@dot.state.fl.us>

Cc: Scott Pedigo <spedigo@nassaucountyfl.com>; George J. Murray <gmurray@nassaucountyfl.com>; Raymond C. Albury <ralbury@nassaucountyfl.com>; Bill Glennon <wglennon@wsbeng.com>; Josh Dalager

<jdalager@wsbeng.com>

Subject: Henry Smith - Change Order No. 0003 For Review

EXTERNAL SENDER: Use caution with links and attachments.

Kim,

Attached is Change Order No. 0003 for your review and concurrence.

Jose Vazquez Jr, P.E.

Area Manager, Contract Administration



[954.295.7476](tel:954.295.7476) (o)

-

219 North Newnan Street

Jacksonville, FL 32202

wsbeng.com

[For a list of WSB employee licenses and certifications visit here.](#)

This email, and any files transmitted with it, is confidential and is intended solely for the use of the addressee.

If you are not the addressee, please delete this email from your system. Any use of this email by unintended recipients is strictly prohibited. WSB does not accept liability for any errors or omissions which arise as a result of electronic transmission. If verification is required, please request a hard copy.

Certificate Of Completion

Envelope Id: 09F973C4-FEF7-4DD1-B2A6-C2E065C2E465

Status: Completed

Subject: Complete with Docusign: CM3670 - CGC Inc - Henry Smith Improvements Change Order Approval Form CO#3

Source Envelope:

Document Pages: 14

Signatures: 5

Envelope Originator:

Certificate Pages: 3

Initials: 1

Scott Pedigo

AutoNav: Enabled

spedigo@nassaucountyfl.com

Envelopeld Stamping: Enabled

IP Address: 50.238.237.26

Time Zone: (UTC-05:00) Eastern Time (US & Canada)

Record Tracking

Status: Original

Holder: Scott Pedigo

Location: DocuSign

8/4/2025 10:20:17 AM

spedigo@nassaucountyfl.com

Signer Events

Signature

Timestamp

Robert Companion

RCompanion@nassaucountyfl.com

Deputy County Manager - County Engineer

Nassau County BOCC

Security Level: Email, Account Authentication
(None)

Signature Adoption: Pre-selected Style
Using IP Address: 50.238.237.26

Sent: 8/4/2025 10:26:55 AM

Viewed: 8/4/2025 10:27:53 AM

Signed: 8/4/2025 10:28:16 AM

Electronic Record and Signature Disclosure:

Not Offered via Docusign

chris lacambra

clacambra@nassaucountyfl.com

OMB Director

Nassau County BOCC

Security Level: Email, Account Authentication
(None)

Signature Adoption: Pre-selected Style
Using IP Address: 50.238.237.26

Sent: 8/4/2025 10:49:08 AM

Viewed: 8/13/2025 4:11:11 PM

Signed: 8/13/2025 4:11:51 PM

Electronic Record and Signature Disclosure:

Not Offered via Docusign

Lanaee Gilmore

lgilmore@nassaucountyfl.com

Procurement Director

Nassau County BOCC

Security Level: Email, Account Authentication
(None)

Signature Adoption: Pre-selected Style
Using IP Address: 50.238.237.26

Sent: 8/13/2025 4:11:53 PM

Viewed: 8/14/2025 6:04:02 PM

Signed: 8/14/2025 6:04:39 PM

Electronic Record and Signature Disclosure:

Not Offered via Docusign

Abigail Jorandby

ajorandby@nassaucountyfl.com

Deputy County Attorney

Nassau BOCC

Security Level: Email, Account Authentication
(None)

Signature Adoption: Pre-selected Style
Using IP Address: 50.238.237.26


Sent: 8/14/2025 6:04:42 PM

Viewed: 8/15/2025 3:00:16 PM

Signed: 8/15/2025 3:00:23 PM

Electronic Record and Signature Disclosure:

Not Offered via Docusign

Signer Events	Signature	Timestamp
Denise C. May, Esq., BCS dmay@nassaucountyfl.com County Attorney Nassau County BOCC Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<i>Denise C. May, Esq., BCS</i> Signature Adoption: Pre-selected Style Using IP Address: 50.238.237.26	Sent: 8/15/2025 3:00:29 PM Viewed: 8/15/2025 3:11:47 PM Signed: 8/15/2025 3:12:23 PM
Taco Pope, AICP tpope@nassaucountyfl.com County Manager Nassau County BOCC Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	 Signature Adoption: Drawn on Device Using IP Address: 50.238.237.26	Sent: 8/15/2025 3:12:25 PM Viewed: 8/15/2025 3:17:50 PM Signed: 8/15/2025 3:17:59 PM
In Person Signer Events	Signature	Timestamp
Editor Delivery Events	Status	Timestamp
Agent Delivery Events	Status	Timestamp
Intermediary Delivery Events	Status	Timestamp
Certified Delivery Events	Status	Timestamp
Carbon Copy Events	Status	Timestamp
Tracy Poore tpoore@nassaucountyfl.com OMB Admin Nassau County BOCC Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<div>COPIED</div>	Sent: 8/4/2025 10:28:18 AM Resent: 8/4/2025 10:49:07 AM
Capital Projects capitalprojects@nassaucountyfl.com Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<div>COPIED</div>	Sent: 8/15/2025 3:18:00 PM
Clerk Services BOCCclerkServices@nassauclerk.com Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<div>COPIED</div>	Sent: 8/15/2025 3:18:01 PM Viewed: 8/15/2025 4:26:50 PM
Procurement procurement@nassaucountyfl.com Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<div>COPIED</div>	Sent: 8/15/2025 3:18:02 PM Viewed: 8/15/2025 4:16:43 PM

Carbon Copy Events	Status	Timestamp
Jose Vazquez Jr jvazquez@wsbeng.com Security Level: Email, Account Authentication (None) Electronic Record and Signature Disclosure: Not Offered via DocuSign	<div>COPIED</div>	Sent: 8/15/2025 3:18:02 PM

Witness Events	Signature	Timestamp
----------------	-----------	-----------

Notary Events	Signature	Timestamp
---------------	-----------	-----------

Envelope Summary Events	Status	Timestamps
Envelope Sent	Hashed/Encrypted	8/4/2025 10:26:56 AM
Envelope Updated	Security Checked	8/4/2025 10:49:07 AM
Envelope Updated	Security Checked	8/4/2025 10:49:07 AM
Certified Delivered	Security Checked	8/15/2025 3:17:50 PM
Signing Complete	Security Checked	8/15/2025 3:17:59 PM
Completed	Security Checked	8/15/2025 3:18:02 PM

Payment Events	Status	Timestamps
----------------	--------	------------